

## 2020 Road Improvement Program - updated 12/20/2019

### Contracted Projects

Road	Seg Begin	Seg End	Length (ft.)	Width (ft.)	Est. Cost	Project Type
<b>Beverly Rd</b>	Hershey Rd	Koser Rd	3,500	24	\$122,449	9.5mm overlay
<b>Bear Creek Rd</b>	Campus Rd	Sheaffer Rd	3,163	22 (est @22.5')	\$103,753	9.5mm overlay
<b>Spring Rd</b>	Ridge Rd	Bear Creek Rd	1,640	22	\$52,598	9.5mm overlay
<b>Harvest Rd</b>	Trail Rd N	Twp. Line	10,391	22	\$635,000	Reclaim & widen to 22' cartway
					<b>\$913,800</b>	

### PW Department Projects

Road	Seg Begin	Seg End	Length (ft.)	Width (ft.)	Est. Cost	Project Type
<b>Country Squire Rd</b>	Oberholtzer Rd	Bellaire Rd	4,075	22	\$92,775	9.5mm overlay
<b>Trail Rd N</b>	Harvest Rd	N of Forest Ln	4,702	22	\$82,860	Drainage & widen to 22' cartway
<b>Quarry Rd</b>	Milton Grove Rd	Twp. Line	3,761	24	\$48,948	Repair previously-widened areas/edges
<b>Stauffer Rd</b>	Mt Pleasant Rd	Grandview Rd	3,681	19	\$72,377	9.5mm overlay
					<b>\$296,960</b>	

### Sealcoating

Road	Seg Begin	Seg End	Length (ft.)	Width (ft.)	Estimated		Length (mi.)	Last Seal/Surface
					Area (sy)	Est. Cost		
<b>Camp Rd</b>	Twp. Line	Twp. Line	6,289	20	13,976	\$19,426	1.19	2013 (seal)
<b>Church Rd</b>	Twp. Line	Creek Rd	4,211	22	10,294	\$14,308	0.80	2013 (seal)
<b>Creek Rd</b>	Colebrook Rd	Camp Rd	8,397	22	20,526	\$28,531	1.59	2013 (seal)
<b>Koser Rd</b>	Mt Gretna Rd	Twp. Line	2,564	20	5,698	\$7,920	0.49	2010 (seal)
<b>Ashwood Ln (2x app)</b>	Hereford Rd	Milton Grove Rd	1,874	28	5,830	\$17,199	0.35	?
<b>Hilltop Cir (2x app)</b>	End	Ashwood Ln	534	28	1,661	\$4,901	0.10	?
<b>Ridgeview Rd S (2x app)</b>	Ridge Rd	Cul-de-sac	1,071	28	3,332	\$9,829	0.20	?
						<b>\$102,115</b>	<b>4.72</b>	

<b>TOTAL</b>	<b>\$1,312,875</b>
--------------	--------------------